GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUATERS: DELHI FIRE SERVICE: NEW DELHI-110001

No: F.6/DFS/MS/SZ/2025/ 2008 Dated: - 20/11/2025

To.

The Authorized Signatory,
Continental Device India Pvt. Ltd.,
C- 120, Naraina Industrial Area,
Phase- 1, New Delhi - 110028.

Sub.: - Regarding renewal of Fire Safety Certificate in r/o M/s. Continental Device India Pvt. Ltd., at Plot No. C- 120, Naraina Industrial Area, Phase- 1, New Delhi - 110028.

Sir,

Please refer to your letter No. Nil, dated 14.10.2025, received in this office through outdoor dairy No. 7081 dated 15.10.2025, on the subject cited above. In this connection it is to inform you that the aforsaid premises have been inspected by the officer concerned of this department on dated 05.11.2025 in the presence of Mr. Yogesh, to check the status of the shortcomings already pointed out by this department vide letter No. F6/DFS/MS/2025/476 dated 26.09.2025. During the course of inspection, it was observed that the shortcomings are not complied.

In view of the above, renewal of 'Fire Safety Certificate' cannot be considered at this stage. You are requested to rectify shortcomings under intimation to this department for taking further necessary action in this matter.

Yours faithfully

(A. K. Malik)
Dy. Chief Fire Officer

Copy to:-

1. The Dy. Commissioner, MCD, Karol Bagh Zone, Anand Parbat, New Delhi.

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEAD QUARTERS : DELHI FIRE SERVICE : NEW DELHI – 110001

C/146

No.F.6/DFS/MS/2025/ 476 Dated: 26 /09/2025

To

Authorized Signatory,
Continental Device India Pvt. Ltd.
C-120, Naraina, Industrial Area,
New Delhi-28.

Sub:- Regarding issuance of fire safety certificate in r/o Continental Device India Pvt. Ltd. C-120, Naraina, Industrial Area, New Delhi.

Sir,

This has reference to your letter no. nil dated 01.09.2025, on the subject cited above in this regard, it is to inform you that the site was inspected by the officer concerned of this department on 15/09/2025 in the presence of Mr. Yogesh and the following shortcomings were observed:-

1. MCP not provided at upper floor, required to be provided at each floor .
2. Hose reel is not covering entire area, required to be extended to left out area.
3. Sprinkler is not provided at basement.
4. Smoke management in basement found nonfunctional.

In view of above, Fire Safety Certificate (FSC) cannot be renewed at this stage. Therefore you are requested to rectify the above shortcomings and re-submit for further consideration in the matter.

Yours faithfully

26/9/2025

(Virendra Singh)
Chief Fire Officer